KADUR DIVISION.

Dated 8th November 1906.

The attention of the public is invited to the notification published in the *Mysore Gazette* dated 15th November 1906, calling for tenders for constructing a 3rd class travellers' bungalow with a Native kitchen at Aldur, Chikmagalur Taluk.

Dated 8th November 1906.

The attention of the public is invited to the notification in the *Mysore Gazette* dated 15th November 1906, calling for tenders for constructing Public Works Department officials' quarters at Balgadi, Koppa Taluk.

H. J. MOLLOY,
Executive Engineer.

WATER-SUPPLY AND STORES DIVISION.

Dated 14th November 1906.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Water-supply and Stores Division, up to 23rd November 1906, for lining with surki concrete and cement-plastering the settling tanks at Vantikoppal, Mysore. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of April 1907.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's office at Bangalore between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 500 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for concrete-lining and cement-plastering tanks at Vantikoppal," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Chief Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Estimate of quantities for lining with surki concrete and cement-plastering the settling tanks at Vantikoppal, Mysore:—

Items of work	Per	Quantity.
Removing the edge stones	S. ft.	2,386
Refixing the edge stones	S. ft.	2,386
Easing slopes with required pitting and filling ...	C. yd.	1,393
Filling concrete for slopes	C. ft.	37,607
Removing old plastering surki	Sqr.	608·00
Plastering with ½" thick cement	,,	973·75
Sundry repairs, etc.	Item	L. S.
Cement pointing	S.qr.	31·82
Cleaning all round the tank after completion of work...	Item	L. S.
Clearing silt from beds of tanks	Item	L. S.

K. SRINIVAS IYENGAR,
for *Executive Engineer.*